## EROSION CONTROL SEQUENCE OF EVENTS

- 1. RECEIVE NPDES COVERAGE FROM SCDHEC.
- 2. HAVE PRE-CONSTRUCTION MEETING ON SITE.
- 3. NOTIFY SCDHEC REGIONAL OFFICE 48 HOURS PRIOR TO ANY LAND DISTURBING ACTIVITIES.
- 4. PHASE I: INITIAL EROSION CONTROL (CV1.2)
- A. CLEARING AND GRUBBING / DEMOLITION ONLY AS NECESSARY FOR INSTALLATION OF PERIMETÉR CONTROLS (SILT FENCE, CONSTRUCTION ENTRANCE, & INLET PROTECTION (EXISTING))
- B. INSTALL CONSTRUCTION ENTRANCE AND PERIMETER CONTROLS.
- C. INSTALL REMAINING EROSION CONTROL MEASURES (INLET PROTECTION) D. BEGIN DEMOLITION / CLEARING AND GRUBBING FOR SOIL STORAGE AREAS ONLY.
- 5. PHASE IIA: GRADING (SEE CV3.1)
- 6. PHASE IIB: STABILIZATION (SEE CV3.1)
- 7. PERMIT CLOSURE (SEE CV3.1)


# SITE CONSTRUCTION NOTES

COORDINATE LOCATION OF FOLLOWING ITEMS WITH CEPSCI INSPECTORS AND/OR ENGINEER. 1. ALL LITTER, TRASH AND CONSTRUCTION DEBRIS SHALL BE COLLECTED, STORED AND DISPOSED OF IN ACCORDANCE WITH SCDHEC SOLID WASTE REGULATIONS. PROVIDE TEMPORARY 4' TALL HOGWIRE - 10' X10' SQUARE STORAGE AREA.

- 2. PROVIDE TEMPORARY SANITARY FACILITIES SHALL BE LOCATED ON A FLAT SURFACE AWAY FROM DRAINAGE FACILITIES, CATCH BASINS, WATERCOURSES AND TRAFFIC CIRCULATION. UPON DISCOVERY, ANY SPILLED MATERIAL SHALL BE CLEANED UP IMMEDIATELY. ALL COLLECTED MATERIAL, CONTAMINATED RAGS AND ABSORBENT MATERIALS SHALL BE DISPOSED OF APPROPRIATELY. LIME SHALL BE SPREAD ON THE CONTAMINATED AREA.
- 3. CEMENT WASTE AND WASHOUT SHALL NOT BE ALLOWED TO DISCHARGE TO STORM DRAINS, DETENTION PONDS OR WATER COURSES. BE COLLECTED IN A DEPRESSED BERMED AREA AND ALLOWED TO HARDEN. IT SHALL NOT BE ALLOWED TO DISCHARGE TO STORM DRAINS, STORM WATER DETENTION FACILITIES OR WATERCOURSES.
  PROVIDE 10' DIAMETER — 8" MULCH TUBE TO CONTAIN CONCRETE WASHOUT

#### **GENERAL NOTES:**

- 1. THESE TRACT CONTAIN 45.0 ACS. PARCEL ID: 080-00-00-063.000 PARCEL ID: 080-00-00-063.000
- 2. OWNER CONTACT: WINSTON ANDERSON SPARTANBURG COMMUNITY COLLEGE PO BOX 4386 SPARTANBURG SC 29305 PHONE: 864-591-3770
- 3. ENGINEER: BLACKWOOD ASSOCIATES INC. PO BOX 366 SPARTANBURG, S.C. 29304
- 4. SURVEY AND TOPOGRAPHIC INFORMATION PROVIDED BY: LAVENDER, SMITH & ASSOCIATES, INC. LAND SURVEYORS & MAPPERS 2900 EAST MAIN STREET SPARTANBURG, S.C. 29307



EROSION CONTROL LEGEND

SILT FENCE

— —882— — — EXISTING CONTOURS

INLET PROTECTION

LIMITS OF DISTURBANCE

TEMPORARY GRAVEL CONSTRUCTION ENTRANCE

PROVIDE CONCRETE WASHDOWN


PROVIDE CONST. DEBRIS ENCLOSURE


SCALE: 1" = 40'


2212 060923


PROVIDE SANITARY FACILITY











REVIEW COMMENTS

CV1.1

# SPECIFICATIONS & NOTES

- 1. CONTRACTOR SHALL VERIFY LOCATION OF UNDERGROUND LINES AND UTILITIES BEFORE EXCAVATION. ADVISE ENGINEER IMMEDIATELY OF ANY VARIATIONS. ALL EXCAVATIONS NEAR THESE LINES SHALL BE WITH CAUTION. CONTRACTOR SHALL VERIFY ALL DIMENSIONS OF EXISTING CONSTRUCTION WHICH AFFECTS NEW CONSTRUCTION. CONTRACTOR RESPONSIBLE FOR ANY DAMAGE DURING CONSTRUCTION AND/OR RELOCATION AS NECESSARY AT CONTRACTOR'S
- 2. CONTRACTOR SHALL VERIFY ALL WORK PRIOR TO CONSTRUCTION, DISCREPANCIES SHALL BE REPORTED TO THE ENGINEER IMMEDIATELY. DISCONTINUE WORK IN ALL AFFECTED AREAS UNTIL RESOLVED BY ENGINEER.
- 3. EARTHWORK SHALL BE TO THE LINES AND GRADES SHOWN. THE CONTRACTOR SHALL PROOF-ROLL THE CONSTRUCTION AREA WITH HEAVY-PNEUMATIC EQUIPMENT. ALL SOFT SPOTS SHALL BE UNDERCUT AND RECOMPACTED WITH SUITABLE STRUCTURAL FILL MATERIAL. ALL FILL COMPACTION SHALL BE 95% OF MAXIMUM PER ASTM D-698 (STANDARD PROCTOR). ALL MATERIAL WITHIN 18 INCHES OF PAVEMENT AND BUILDING SUBGRADE SHALL BE COMPACTED TO 98% OF MAXIMUM. FILL MATERIAL SHALL NOT CONTAIN ORGANIC MATERIAL, DEBRIS OR ROCKS. WHERE FILL IS TO BE PLACED, ALL EXISTING VEGETATION, ROOTS AND OTHER ORGANIC MATTER DOWN TO 12 INCHES BELOW EXISTING GRADE SHALL BE STRIPPED AND DISPOSED OF AS DIRECTED. FILL SHALL BE PLACED IN SUCCESSIVE LAYERS OF NOT MORE THAN 8 INCHES LOOSE THICKNESS. EACH LAYER SHALL BE SPREAD EVENLY AND COMPACTED AS SPECIFIED BEFORE THE NEXT LAYER IS PLACED.
- 4. THE CONTRACTOR SHALL REMOVE ALL DEBRIS INCLUDING PAVEMENT, CONCRETE, AND UNSUITABLE MATERIAL FROM THE SITE. ALL AREAS UNDER EXISTING PAVEMENT SHALL BE SCARIFIED BEFORE PLACING STRUCTURAL FILL MATERIAL.

- 5. CATCH BASINS SHALL BE IN ACCORDANCE WITH SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS
- (2000) AND SCDOT STANDARD DRAWINGS FOR ROAD CONSTRUCTION. 6. STORM SEWER SHALL BE LAID ON A MINIMUM TYPE "C" BEDDING FOR DEPTHS UP TO 21', FOR DEPTHS GREATER THAN 21' USE TYPE "B" BEDDING. PLACE BELL OR BED GROOVE END UP GRADE WITH THE SPIGOT OR TONGUE FULLY INSERTED. EACH JOINT SHALL BE CHECKED FOR ALIGNMENT AND GRADE AS THE WORK PROCEEDS. APPROVED BACKFILL MATERIAL SHALL BE PLACED CAREFULLY ALONG THE PIPE AND COMPACTED UNDER HAUNCHES. MATERIAL SHALL BE BROUGHT UP EVENLY IN LAYERS ON BOTH SIDES OF THE PIPE AND TO ONE FOOT ABOVE THE TOP OF THE PIPE. MATERIAL SHALL BE PLACED IN A MANNER SO AS NOT TO DISPLACE OR DAMAGE THE INSTALLED PIPE. BACKFILL SHALL BE PLACED AND COMPACTED
- IN LAYERS AS SPECIFIED. 7. REINFORCED CONCRETE PIPE (RCP) SHALL BE: CLASS III — DEPTHS 0'-14' TYPE "C" BEDDING CLASS IV - DEPTHS 14.1'-21' TYPE "C" BEDDING. CLASS IV - DEPTHS 21.1'-27' TYPE "B" BEDDING. CLASS V - DEPTHS 27.1'-41' TYPE "B" BEDDING. ALL RCP SHALL HAVE BUTYL RUBBER GASKET SEALANT UNLESS OTHERWISE SPECIFIED. JOINTS AND FITTINGS / ACCESSORIES SHALL BE COMPATIBLE WITH PIPE. SEE BEDDING DETAILS.
- 8. ASPHALT PAVING SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE DETAILS AND THE SOUTH CAROLINA D.O.T. STANDARD SPECIFICATION FOR HIGHWAY CONSTRUCTION.
- 9. CONCRETE SHALL BE 4,000 PSI CONCRETE MINIMUM STEEL REINFORCEMENT SHALL BE ASTM A615, GRADE 60.

# SITE PLAN NOTES

- 1. CONTRACTOR SHALL IDENTIFY THE LOCATION AND ELEVATIONS
- 2. ANY DISCREPANCIES FROM THE DRAWINGS SHALL BE REPORTED
- 3. ALL DIMENSIONS ARE TO THE FACE OF CURB, FACE OF THE BUILDING, OR THE EDGE OF PAVEMENT
- 5. FOLLOW ALL S.C.D.O.T., AND OSHA GUIDELINES AND REGULATIONS WHEN CONSTRUCTING UTILITY AND DRAINAGE TIES IN HIGHWAY.


### **GENERAL NOTES:** 1. THESE TRACT CONTAIN 45.0 ACS. PARCEL ID: 080-00-00-063.000 PARCEL ID: 080-00-00-063.000

2. OWNER CONTACT: WINSTON ANDERSON SPARTANBURG COMMUNITY COLLEGE PO BOX 4386 SPARTANBURG SC 29305


PHONE: 864-591-3770

3. ENGINEER: BLACKWOOD ASSOCIATES INC. PO BOX 366 SPARTANBURG, S.C. 29304

4. SURVEY AND TOPOGRAPHIC INFORMATION PROVIDED BY: LAVENDER, SMITH & ASSOCIATES, INC. LAND SURVEYORS & MAPPERS 2900 EAST MAIN STREET SPARTANBURG, S.C. 29307








SHEET ISSUE:


A 04.25.22 PERMIT SET B 11.15.22 **REVIEW COMMENTS** C 06.09.23 BID SET

SITE **PLAN**  06.09.2023

CV2.1

# OF ALL UTILITIES ON SITE BEFORE CONSTRUCTION. TO THE ENGINEER IMMEDIATELY.





### SCDHEC/COUNTY STANDARD NOTES

- 1. IF NECESSARY, SLOPES, WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE. 2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY
- CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW. \* WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE. \* WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
- 3. ALL SEDIMENT AND ERSION CONTROL DEVICES SHALL BE INSPECTED ONCE CALENDAR EVERY WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY, OR INCORRECTLY, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF
- 4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF
- 5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCÉ CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- 6. THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED. 7. RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE

AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL

FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN

IN ACCORDANCE WITH S.C REG. 72-300 ET SEQ. AND SCR100000. 8. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT

SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.

9. ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOS.

- 10. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICAL'S THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
- 11. A COPY OF THE SWPPP, INSPECTIONS RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATA OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.
- 12. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORALITY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.
- 13. MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL.
- 14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE.
- 15. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPS (SEDIMENT BASINS, FILTER BAG, ETC.).
- 16. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:

OPERATION AND MAINTENANCE; AND

- \* WASHWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL: \* WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS; \* FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT
- \* SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING. 17. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- 18. IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPS MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.
- 19. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.
- 20. CONTRACTORS ARE REQUIRED TO HAVE RAIN GAUGES AT THE CONSTRUCTION SITE AND THE RAIN TOTALS DOCUMENTED FOR REVIEW.

## EROSION CONTROL **SEQUENCE OF EVENTS**

- 5. PHASE IIA: GRADING (CV3.1)
- A. COMPLETE CLEARING AND GRUBBING FOR INSTALLATION OF STORM DRAINAGE. B. PLACE INLET PROTECTION AROUND ALL NEW CATCH BASINS.
- C. COMPLETE TOPSOIL REMOVAL AND/OR STORAGE FOR REMAINDER OF SITE. D. COMPLETE REMAINING GRADING, STORM DRAINAGE, AND SITE UTILITIES. E. COMPLETE GRADING OPERATIONS.

#### 6. PHASE IIB: STABILIZATION (CV3.1)

- A. APPLY GRASSING IN ACCORDANCE WITH GRASS NOTES. B. INSPECT AND MAINTAIN ALL EROSION CONTROL AS INDICATED IN GRADING NOTES. C. PERMANENT GRASS SHALL BE INSTALLED FOR ALL AREAS AT FINAL GRADE AND
- IN SEASON INDICATED ON GRASS NOTES. D. AFTER COMPLETION OF CONSTRUCTION AND THE SITE IS STABILIZED: (A) REMOVE ALL ACCUMULATED SEDIMENT FROM SEDIMENT TRAPPING MEASURES
- AND SPREAD EVENLY ACROSS THE SITE. (B) REMOVE ALL TEMPORARY EROSION CONTROL MEASURES (SILT FENCE, INLET PROTECTION, & RIPRAP BERM). GRASS ANY DISTURBED AREAS.

#### 7. PERMIT CLOSURE

A. THE NOTICE OF TEMRINATION CAN BE SUBMITTED TO SCDHEC UPON THE SITE REACHING A MINIMUM OF 70% UNIFORM SITE STABLIZATION.


## GRADING PLAN LEGEND

SILT FENCE INLET PROTECTION

 $\implies \implies$ 

LIMITS OF DISTURBANCE EXISTING CONTOURS ——882— PROPOSED CONTOURS

DIRECTION OF POSITIVE DRAINAGE



Know what's **below.** 


YOU ARE REQUIRED TO CALL AT LEAST 3 WORKING DAYS BEFORE YOU DIG http://www.call811.com/


Call before you dig.














2212 060923

